

**WATER QUALITY MONITORING PLAN  
WHITE STREET LANDFILL  
PHASE I AND II AREAS  
WHITE STREET  
GREENSBORO, NORTH CAROLINA**  
S&ME Project No. 1584-98-081

Prepared for:  
The City of Greensboro


Prepared by:  
S&ME, Inc.  
3718 Old Battleground Road  
Greensboro, North Carolina 27401

December 2007






I hereby certify this 14th day of December, 2007, that this report was prepared by me or under my direct supervision.

  
Edmund O. O. Edwards, II, G.  
Environmental Department Manager

The seal is circular with "NORTH CAROLINA" at the top, "LICENSED" in the middle, and "SEAL 1246" at the bottom. The name "Edmund O. O. Edwards, II, G." is written across the seal, and "Environmental Department Manager" is written below it.

Technical review performed by:

  
Wayne H. Watterson, P.E.  
Senior Engineer

The signature is written in cursive over a horizontal line. Below the line, the name "Wayne H. Watterson, P.E." and title "Senior Engineer" are printed.

## TABLE OF CONTENTS

1. PURPOSE AND INTENT .....	1
2. DESCRIPTION OF PLAN COMPONENTS.....	1
3. DATA COLLECTION PROCEDURES.....	1
3.1 Water Quality Sampling Locations .....	1
3.1.1 Background Wells .....	1
3.1.2 Downgradient (Detection) Wells .....	2
3.1.3 Surface Water Sample Locations .....	2
3.2 Monitoring Well Data Collection.....	2
3.2.1 Equipment Specifications.....	3
3.2.2 Ground Water Level Data Measurements.....	4
3.2.3 Well Evacuation.....	4
3.2.4 Sample Collection.....	5
3.2.5 Surface Water Sampling Procedures.....	7
3.3 Decontamination Procedures .....	8
3.4 Sample Parameters and Frequency.....	8
3.4.1 Ground Water Analytical Methods .....	8
3.4.2 Ground Water Sampling Frequency.....	8
3.4.3 Surface Water Analytical Methods .....	8
3.4.4 Surface Water Sampling Frequency.....	8
3.4.5 QA/QC Procedures.....	8
4. STATISTICAL EVALUATION OF MONITORING DATA .....	9
4.1 ANOVA (Parametric) .....	9
4.2 ANOVA (Non-Parametric) .....	9
4.3 Tolerance/Prediction Intervals .....	9
4.4 Control Charts .....	10
4.5 Other Statistical Methods.....	10
5. DATA REPORTING PROCEDURES.....	11
5.1 Ground Water Direction and Flow Measurements .....	11
5.2 Seepage (Pore Water) Calculations.....	11
5.3 Detection Monitoring Reporting.....	11
5.4 Assessment Monitoring Program .....	11
5.4.1 Analytical Parameters and Sampling Frequency.....	11
5.4.2 Assessment Monitoring Reporting.....	12
5.4.3 Establishment and Reporting of Background Concentrations .....	12
5.4.4 Evaluation of Background and Assessment Data .....	12
5.5 Assessment of Corrective Measures .....	12
APPENDIX I.....	I-1
TABLE 1a .....	I-2
TABLE 1b.....	I-3
TABLE 2 .....	I-5
TABLE 3a .....	I-6
TABLE 3b.....	I-9
TABLE 4 .....	I-13
APPENDIX II.....	II-1
APPENDIX III .....	III-1

## **WATER QUALITY MONITORING PLAN**

### **1. PURPOSE AND INTENT**

The purpose of this plan is to provide a program which describes the collection and evaluation of ground water monitoring samples collected from compliance wells installed within the uppermost aquifer adjacent to the Phase I (closed) and Phase II (closed MSW and active C&D) portions of the White Street Landfill in Greensboro, North Carolina, and surface water quality samples from the same vicinity. The intent of this plan is to provide detection monitoring throughout the active life and post-closure care period at the White Street Landfill.

This plan was prepared in accordance with the rules codified under the North Carolina Solid Waste Management 15A NCAC 13B, Sections .1630 through .1637 under the guidance of a North Carolina Licensed Geologist. The water quality monitoring plan is effective in providing early detection of any release of hazardous constituents from the MSWLF unit to the uppermost aquifer, so as to be protective of public health and the environment.

### **2. DESCRIPTION OF PLAN COMPONENTS**

This plan describes the basic field data collection and reporting requirements for the collection of ground water and surface water quality samples for the evaluation of site conditions relating to the disposal of solid waste at the above referenced facility. Sections of this plan describe the rationale behind background and downgradient well selection, selection of surface water sample locations, well purging and sampling techniques, surface water sampling techniques, decontamination procedures, ground water and surface water analytical parameters with quality assurance/quality control (QA/QC) requirements, and statistical analysis options, and reporting requirements.

### **3. DATA COLLECTION PROCEDURES**

#### **3.1 Water Quality Sampling Locations**

The following sections discuss the general rationale used to select the upgradient (background) compliance wells and the downgradient (detection) compliance wells based on available geologic and hydrogeologic data. All well locations were selected on their basis to provide water quality data from the uppermost aquifer beneath the facility. The rationale for selection of surface water monitoring points is also discussed.

##### **3.1.1 Background Wells**

Using the historical water-table elevation data collected during multiple ground water monitoring events at the facility, background compliance wells were selected on the basis of hydraulic position in relation to the solid waste management units. Wells hydraulically "upgradient" of the unit were selected first. Existing ground-water monitoring well MW-13 fit this scenario for Phase I while existing monitor well MW-14 fit this scenario for Phase II. **Tables 1a and 1b** summarize the existing background monitoring wells for the Phase I and Phase II portions of the landfill, respectively, and their estimated distances

from their respective compliance boundaries. The location of these wells can be seen on **Figures 1 and 2** located in **Appendix II**.

### **3.1.2 Downgradient (Detection) Wells**

The hydrogeologic and geologic characteristics of the facility and surrounding land, and the quantity, quality, and direction of ground water flow, were evaluated to determine the appropriate selection of downgradient (detection) wells. In addition to the criteria above, the distance of each proposed well relative to the waste unit (less than 250 feet) and the boundary of the property (50 feet or greater) were also considered. **Tables 1a and 1b** summarize the downgradient (detection) monitoring wells for the Phase I and Phase II portions of the landfill, respectively, and their estimated distances from their respective compliance boundaries. The location of these wells can be seen on **Figures 1 and 2** located in **Appendix II**. Soil boring logs and monitoring well construction record drawings for these wells are included in **Appendix III**.

### **3.1.3 Surface Water Sample Locations**

The locations of the five surface sample points are referenced on **Figures 1 and 2**. SW-2 is located on a southern tributary of North Buffalo Creek several hundred feet before it joins the main creek west of the landfill entrance. SW-3 is located on North Buffalo Creek just below the North Buffalo Creek Wastewater Treatment Plant outfall, upstream of the landfill. SW-4 is downstream of the landfill at the U.S.G.S. gauging station on North Buffalo Creek. Finally, SW-5 is located downstream of the landfill on another southern tributary of North Buffalo Creek.

## **3.2 Monitoring Well Data Collection**

The following data will be collected and reported during the period of performance for this water quality plan. A brief discussion on the collection of and analysis of these data is provided in the sections to follow. Field conditions (e.g., temperature, weather conditions, purge start/stop times, sample collection start/stop times, etc.) during each sampling event will be recorded on Daily Field Report forms (**Attachment 1**), or equivalent. The primary objectives of groundwater sampling are (1) to obtain a representative groundwater sample and (2), to prevent the sample from being altered or contaminated during withdrawal from the well or during sample preparation.

The City of Greensboro has elected to use dedicated sampling pumps to collect groundwater samples from monitor wells around the landfill. With proper techniques for low-flow purging and sampling, the pumps offer the potential of obtaining groundwater samples with lower turbidity than may be obtainable with bailers. However, the City reserves the right to use conventional sampling methods (dedicated bailer sampling) to sample the wells in the event of pump malfunction, or as may be required by site specific conditions.

The following sections discuss specifications and procedures applicable to both sampling methods. Detailed discussion of proper sampling procedures for each method can be found in relevant guidance documents prepared by the North Carolina Division of Waste

Management Solid Waste Management Section, or the United States Environmental Protection Agency (USEPA).

### **3.2.1 Equipment Specifications**

It is the intent of these specifications that the sampling pump or the bailer be constructed of inert materials. Sample collection equipment should not alter the analyte concentrations, cause loss of analytes via sorption, or result in analytes desorption, degradation or corrosion of the pump components. Sampling equipment should cause minimal sample agitation and should be selected to minimize sample contact with the atmosphere during sample transfer. The following section discusses the specifications of the dedicated pumps and bailers.

#### **3.2.1.1 Dedicated Pneumatic Sampling Pumps**

Dedicated sampling pumps shall be all-pneumatic, bladder pumps driven by a portable air controller supplied with compressed air from a portable oil less air compressor or compressed air bottle. Pump effluent will pass through a portable flow-through cell and water analyzer which will monitor temperature, pH, conductivity, oxidation reduction potential (ORP), and dissolved oxygen to indicate when stabilization has occurred.

The sampling pump shall be a positive gas displacement bladder pump. The pump shall be constructed such that no gas or liquid is introduced into the well during the pumping operation. The pump shall be constructed of 316 stainless steel with a Teflon bladder. Bladders shall be field-replaceable and warranted for a period of 10 years. Bladder clamps shall also be constructed of 316 stainless steel. Pumps will be equipped with a screen having an opening not exceeding 0.012 inches. Sample pumps shall employ self polishing hard seat internal check valves.

The manufacturer shall warrant all pumps to be of new construction and shall certify all pumps and screens to be free of all EPA Method 601, 602, base neutral, and acid extractable contaminants. Certification and copies of the analytical reports with test batch numbers will be provided with each pump. Pump airline and discharge tubing shall be of new material, sized to match fittings supplied with each pump. The tubing bundle will consist of polyethylene air supply line heat bonded to a Teflon-lined polyethylene water supply line. The sample discharge tube shall provide a separate flow path without exposure to pump drive air and shall assure that discharge from the pump contacts only the Teflon inner tubing. The manufacturer shall certify that only virgin PTFE (Teflon) has been used in the manufacture of the inner tubing.

The pump air supply line and discharge tubing shall be attached to a well head assembly that will allow attachment of the air supply line to the well head with use of a quick - connect fitting. The well head assembly shall have an opening to allow measurement of water level with an electric water level probe. The discharge piping shall allow attachment of a Teflon elbow (QED part number 34485 or equivalent) to facilitate collection of the sample.

The air compressor shall be portable, gasoline powered, of an oilless design to prevent potential contamination to the sample in the event of malfunction and capable of supplying air to the controller at a minimum of 4.3 SCFM at 100 psi. The air compressor shall be supplied with a minimum of 40 feet of air line to allow operation of the gasoline engine downwind of the well during sampling.

The controller shall be capable of regulating both pressure and duration of bladder inflation and deflation cycles to allow optimum pump performance. A pause feature shall be provided to allow manual discharging and filling of sample during sample collection.

#### **3.2.1.2 Manual Sampling Equipment**

Manual sampling will be performed using Teflon bailers previously cleaned in a laboratory in accordance with procedures from the North Carolina Water Quality Monitoring Guidance Document for Solid Waste Facilities. Each bailer shall be cleaned, air-dried, and wrapped in aluminum foil in the laboratory prior to shipment to the field. Following sampling, the bailers shall be returned to the laboratory for cleaning and storage. A separate laboratory cleaned bailer is required for each monitoring well. Field cleaning of sampling bailers will not be allowed.

The bailer line should consist of either (1) Teflon coated wire (2) single strand stainless steel wire (3) other monofilament line or (4) nylon rope. In order to avoid cross-contamination, new bailer should be used at each well, for each sampling event.

#### **3.2.2 *Ground Water Level Data Measurements***

Prior to purging of each well for water quality sample collection, static water level (and total well depth) will be measured to the nearest  $\pm 0.01$  foot using an electronic water level probe and recorded on a Daily Field Report form, or equivalent. The water level probe will be decontaminated prior to, and between, each use by washing in a non-phosphate laboratory detergent (Liquinox or equivalent) wash, followed by a distilled water rinse. Each measurement will be made from a reference point established on the inside of the top of the PVC well casing. The elevation at the top of each well casing will be established by a North Carolina Registered Land Surveyor (RLS) to within  $\pm 0.01$  foot. The horizontal position of each well will be established using North Carolina Plane Coordinates.

These data will be used to calculate the volume of standing water in each well and will provide information concerning well integrity (e.g., identify the presence of excessive siltation, casing breaches).

#### **3.2.3 *Well Evacuation***

Because the standing water in the well may not represent in-situ groundwater quality, stagnant water should be removed from the well and filter pack prior to sampling. The evacuation (purging) procedure should ensure that the samples collected from the well are representative of groundwater quality in the vicinity of the well. In general, evacuation should be continued until certain geochemical parameters stabilize. Practice has demonstrated that these parameters usually stabilize with manual bailing of two to three

well volumes. By using low-flow pumping rates during well evacuation, stabilized conditions can be obtained with removal of less than 1 well volume.

### 3.2.3.1 Low-Flow Well Evacuation With Dedicated Pumps

Purging should be performed by removing water from the well at a flow rate as close to actual groundwater flow rate. If this determination is impractical at the time, a default purging rate of around 100 ml. per minute should be used. The purge rate should be low enough that recharge water does not become overly agitated or to lessen the draw of colloids into the well bore. Purging should be continued until field measurements of pH, conductivity, turbidity<sup>1</sup>, oxidation-reduction potential (ORP), and dissolved oxygen<sup>2</sup> in-line measurements have stabilized to within approximate 10 percent over at least 3 consecutive measurements over time.

### 3.2.3.2 Well Evacuation Techniques Using a Bailer

Determination of the quantity of water to be bailed from each well will be made by calculating the volume of water in the well. This quantity can be made by subtracting the depth to the water surface from the total depth of the well as measured from the top of the well casing, and multiplying the difference by the cross-sectional area inside the well casing. For example, a 2-inch diameter (I.D.) pipe (Schedule 40) has 0.1632 gallons per foot of pipe length. Therefore, five times the volume of a 2-inch diameter well having a seven-foot water column would be equal to 5.7 gallons (0.1632 gal/ft x 7 ft x 5 volumes). For moderate to high yield wells, a minimum of 3 to 5 times the volume of water standing in the well will be removed prior to sampling. For low yield wells, a minimum of 1.5 times the well volume will be removed if evacuated to dryness.

During manual purging, the bailer will be slowly lowered into the water column until full, then slowly retrieved from the well. The quantity of water removed from the well can be gauged by filling a calibrated bucket. Insertion of the bailer into the water column should be performed gently to minimize turbidity that results from redevelopment of the well. The bailer should not contact the ground surface or the container during well purging.

### 3.2.4 *Sample Collection*

It is desirable to have the analytical laboratory prepare and supply the sample containers in a protective cooler or transpack. Delivery of the empty containers by the laboratory to the sampler will be noted on the Chain of Custody. The same Chain of Custody will remain with the containers until they are delivered to the laboratory for testing.

A complete set of precleaned and prelabeled sample bottles will be removed from the cooler, prior to lowering the bailer in the well, or turning on the pump to collect the sample. Once collected, a portion of the sample from the bailer or pump (for each well) will be transferred into a fresh container. Preservatives will be added as necessary (in accordance with EPA Methods SW-846) to the sample bottles either by the laboratory or in the field immediately prior to sampling. One trip blank prepared by the laboratory will

---

<sup>1</sup> When turbidity is greater than 10 NTUs

<sup>2</sup> When final dissolved oxygen concentrations are less than 1 mg/L, the stabilization criteria will be  $\pm 0.2$  mg/L.



be analyzed each event. Equipment blanks are not recommended when the dedicated pumps are used for well evacuation and sampling. An equipment blank will be used when wells are evacuated and sampled using bailers.

Because water samples are analyzed for various parameters, several types of containers are required. The sample collection will proceed as follows: volatile organic compounds (VOCs) will be collected first in 40 ml glass vials with Teflon caps. The vials will be filled completely with no headspace remaining. Samples to be analyzed for inorganic constituents (metals) will be collected next. The containers are usually plastic cubes or bottles that have acid placed in the container as a preservative. These containers should not be rinsed prior to sampling.

If organic contamination is suspected, additional samples may be analyzed for semi-volatiles. Semi-volatiles, if required, will be collected following the inorganic compounds. Generally, the semi-volatiles are collected in a 1-liter amber bottle. Water samples to be analyzed for radiological parameters will be collected next, followed by bacteriological parameters. The radiological samples will be collected in 1-liter bottles and the bacteriological samples in 120-ml plastic bottles containing sodium thiosulfate as a preservative.

After transferring the sample to the container, it will be sealed and placed in chilled cooler or transpack pending completion of the sampling event and delivery to the laboratory. After completion of sampling at each well location, the well will be capped and secured. The samples will be secured in the coolers, or transpacks, and shipped or delivered to the laboratory as soon as practical.

#### 3.2.4.1 Sample Collection With Dedicated Pumps

Following stabilization of field parameters, samples should be collected directly from the discharge port of the pump tubing, prior to passing through the flow-through cell. The purging pumping rate should be maintained or slightly reduced for sampling. Flow rates should be low enough to prevent aeration of the samples. For the volatile organic containers, the vials should be filled so that there are no air bubbles in the sample. There should be no headspace remaining in the vial after sample collection.

All sample containers will be labeled with well I.D. number, sample date, sample time, sampler initials, and the parameters in which to be analyzed. Each sample will be placed on ice for transport to a North Carolina Certified (15A NCAC 2H .0800) Laboratory for analysis. A Chain of Custody (see Attachment 2) will accompany the samples to the laboratory. **Table 2** summarizes the various Appendix I and II analytical parameters with their recommended sample container(s), preservatives, minimum sample volume, and maximum holding times.

#### 3.2.4.2 Sample Collection with Bailers

Ground water samples will be collected within 24 hours of purging. Samples will be collected using either disposable Teflon<sup>®</sup> bailers or decontaminated (non-dedicated) Teflon<sup>®</sup> bailers. If disposable Teflon<sup>®</sup> bailers are used, they will be certified to have been

cleaned according to EPA protocol. This certification will accompany the well sampling and analysis data. If non-dedicated bailers are used, they shall be laboratory decontaminated prior to each use, in accordance with the decontamination procedures outlined in Section 3.3 of this document. New nylon cord and sampling gloves will be used at each new well location during sampling. All sampling materials not to be reused (e.g. surgical gloves, nylon cord, disposable Teflon<sup>®</sup> bailers) will be properly disposed of.

Ground water samples will be collected in the order of sensitivity to volatilization as follows:

- Volatile Organic Compounds (VOCs)
- Semi-Volatile Organic Compounds
- Total Metals
- Cations and Anions (including pH, Temperature, and Specific Conductance)

All samples for total metals analysis will be collected unfiltered. Volatile organics will be collected in 40 ml vials without headspace (i.e. no air bubbles). Bailers will be gently lowered to the water table so as not to agitate the ground water to be sampled.

All sample containers will be labeled with appropriate well ID number, sample date, sample time, sampler initials, and the parameters for which to be analyzed. Each sample will be placed immediately on ice for transport to a North Carolina DEM Certified (15A NCAC 2H .0800) Laboratory for ground water analysis. A Chain-of-Custody Record (see Attachment 2) will accompany the samples to the laboratory. **Table 2** summarizes the various Appendix I and II analytical parameters with their recommended sample container(s), preservative, minimum sample volume, and maximum holding times.

### **3.2.5 Surface Water Sampling Procedures**

Surface water samples will be collected at the designated locations using the following procedures.

1. Gently lower the sample container into the water and rinse the container once prior to sample collection (unless a pre-measured amount of a preservative has been added).
2. Submerge the container (mouth down) below the water level and orient the mouth of the container towards the current at a depth of approximately six inches below the surface (do not breach the surface with the mouth of the container).
3. Lift the container from the water and secure the lid on the container. Volatile organics will be collected in 40 ml vials without headspace (i.e. no air bubbles).

During times of low stream flow, the container will be slowly moved side to side during filling. If water levels in the stream are too low to facilitate submerging the container, a small pool will be created and allowed to fill with water prior to sample collection (after settlement of suspended sediment). New surgical gloves will be worn for both the upstream (background) and downstream (detection) sampling events.

### 3.3 Decontamination Procedures

All non-dedicated sampling and data collection equipment will be decontaminated prior to each use, except as noted elsewhere in this plan, in accordance with the following procedures:

1. Tap water and non-phosphate laboratory detergent (Liquinox or equivalent) wash.
2. Tap water rinse.
3. 10% nitric acid rinse (delete this step for stainless steel item decon).
4. Rinse with deionized or distilled water.
5. Rinse with high grade isopropanol and allow to air dry.
6. Wrap with aluminum foil, if necessary, to prevent contamination during storage or transport.

### 3.4 Sample Parameters and Frequency

#### 3.4.1 Ground Water Analytical Methods

The ground-water samples collected from the background and downgradient compliance wells at the Phase I portion of the landfill will be analyzed, at a minimum, for the constituents listed in the current Solid Waste Section requirements for sampling at Closed Sanitary Landfills. **Table 3a** summarizes these constituents as well as the preferred analytical method and Solid Waste Section Limit (SWSL) for each constituent. The ground-water samples collected from the background and downgradient compliance wells at the Phase II portion of the landfill will be analyzed, at a minimum, for the constituents listed in Appendix I of 40 CFR Part 258 entitled "Appendix I Constituents for Detection Monitoring." **Table 3b** summarizes Appendix I constituents as well as the preferred analytical method and Solid Waste Section Limit (SWLS) for each constituent.

#### 3.4.2 Ground Water Sampling Frequency

Water quality samples will be collected on a semiannual basis for the life of the facility and the required post-closure monitoring period, except as required by the State.

#### 3.4.3 Surface Water Analytical Methods

Surface water samples will be analyzed for the same analytical parameters (Appendix I list) as the Phase II ground-water quality samples.

#### 3.4.4 Surface Water Sampling Frequency

Surface water samples will be collected on a semiannual basis for the life of the facility and the required post-closure monitoring period, except as required by the State.

#### 3.4.5 QA/QC Procedures

One trip blank and one field blank will be taken during each sampling event to provide QA/QC evaluation of decontamination procedures, sampling handling procedures, and container shipping procedures. Trip blanks will be analyzed for volatile organics only, while equipment blanks will be analyzed for the full analytical suite. A duplicate water quality sample will be collected at least once a year from a selected monitoring well in order to check laboratory accuracy and QA/QC. Duplicate samples will be analyzed for the entire parameter list.

## **4. STATISTICAL EVALUATION OF MONITORING DATA**

Five methods have been deemed acceptable by the NCDENR for the statistical evaluation of quality data from MSWLF facilities. Each of these tests have inherent advantages and disadvantages which render them more or less useful, depending on site and data set characteristics. Each method is briefly described below.

### **4.1 ANOVA (Parametric)**

A parametric analysis of variance (ANOVA) followed by multiple comparison procedures to identify specific sources of difference is the preferred method for a facility in the early stages of monitoring. The procedures include estimation and testing of the contrasts between the mean concentrations at each compliance well and those at the background well for each constituent.

Analysis-of-variance models are used to analyze the effects of an independent variable on a dependent variable. For monitoring data, a well or group of wells is the independent variable, and the aqueous concentration of certain constituents or of a specified contaminant or contaminants is the dependent variable. An analysis-of-variance can determine whether observed variations (differences) in aqueous concentrations between compliance and background wells are statistically significant. Use of analysis-of-variance models is appropriate in situations where background concentrations of specific constituents can be determined and the data are normally or log normally distributed. The constituents which are most appropriately evaluated using ANOVA approaches are naturally occurring metals and other geochemical parameters such as chloride, nitrate-N, and specific conductivity.

### **4.2 ANOVA (Non-Parametric)**

A non-parametric analysis of variance (ANOVA) based on ranks followed by multiple comparison procedures to identify specific sources of difference can be used when the data are not normally distributed and cannot be transformed into a log-normal distribution. The procedure includes estimation and testing of the contrasts between the median of each compliance well and the background well for each constituent. This is a non-parametric procedure, which means that the laboratory values are not used; only the relative ranks are used.

### **4.3 Tolerance/Prediction Intervals**

A tolerance interval or a prediction interval for each constituent is established from the background data. The concentration of each constituent in each compliance well is compared to set upper (or lower) tolerance or prediction limits.

Tolerance intervals define, with a specified probability, a range of values that are expected to contain a discrete percentage of the sample population (95%). Tolerance intervals are most appropriate for facilities which do not have high degrees of spatial variability between background and compliance well (e.g. areas underlain by homogeneous geologic materials such as granitic saprolite). With monitoring data, tolerance intervals can be constructed from concentrations found in the background well(s); these intervals are most often expressed as limits defined by the mean

background well concentration plus a population size determined multiple of the standard deviation of the mean. Possible contamination is indicated when concentrations of the specified constituent(s) at the compliance well(s) plot above the calculated tolerance interval limits.

Prediction intervals are intervals in which the user is confident at a specified percentage (95%) that the next observation will lie within the interval, and are based on the number of previous observations, the number of new measurements to be made, and the level of confidence that the user wishes to obtain. This method of statistical analysis can be used in both detection and compliance monitoring programs. The mean concentration and standard deviation are estimated from the background wells. In a compliance monitoring program, prediction intervals are constructed from compliance well concentrations beginning at the time the facility entered the compliance monitoring program. Each compliance well observation is tested to determine if it lies within the prediction interval. If it is greater (or lower) than the historical prediction limits, water quality has deteriorated to such a point that further action may be warranted.

#### **4.4 Control Charts**

A control chart approach provides control limits for each constituent which can be used to evaluate data produced by repeated sampling and analysis for each well in the monitoring network. This is an intrawell approach which does not involve a comparison between background and compliance wells. If any compliance well has a value or a sequence of values that lie outside of the control limits for that constituent, this may constitute statistically significant evidence of contamination.

Control charts are based on repeated independent sampling events conducted over time and may be developed for each constituent of interest. Different statistical measurements, such as the means, standard deviation and mean of replicate values at a point in time, are computed and plotted graphically together with upper predetermined limits on a chart in which the x-axis represents time. When a data point plots above these boundaries, the process is "out of control," and when it plots below the boundaries, the process is "in control." Control charts can be used to analyze the inherent statistical variation of monitoring data, to note aberrations, and to detect trends in the data. Further investigation of "out of control" points is necessary before taking any direct action. A control chart can be constructed for each constituent in each well to monitor the concentration of that constituent over time. New samples can be compared to the historical data from the well to determine if the well is "in or out of control." Control charts can also be used to evaluate monitoring data when these data have been adjusted and/or transformed as appropriate.

#### **4.5 Other Statistical Methods**

Other statistical methods submitted by the facility owner or operator and approved by the NCDEHNR may also be used. This could include development of confidence intervals in which data are compared to Federal or State established maximum contaminant limits (MCLs) or alternate contaminant limits (ACLs).

## **5. DATA REPORTING PROCEDURES**

A report will be prepared which summarizes the sampling event, including field observations relating to the condition of the monitoring wells, well completion records and boring logs for background and downgradient wells, field observation data, laboratory data, statistical analysis, sampling methodologies, quality assurance and quality control data, information on flow direction, and calculations of flow rate.

### **5.1 Ground Water Direction and Flow Measurements**

A water table elevation will be calculated for each monitoring well using surveyed top-of-casing elevations prepared by a North Carolina registered land surveyor. Calculated potentiometric surface elevations, for each sampling event, will be placed on a scaled base map of the facility beside each respective monitoring point and contoured to produce a water table potentiometric surface map depicting potential ground water flow direction(s) across the landfill.

### **5.2 Seepage (Pore Water) Calculations**

In addition, estimated ground water flow velocities for each compliance monitoring point will be calculated for each water quality sampling event. Using the static water table potentiometric data, measured aquifer material porosity and hydraulic conductivity values developed during the site study, and the calculated hydraulic gradients at each monitoring well for the respective sample event, an estimated seepage (pore water) velocity at each monitoring well will be calculated to evaluate potential contaminant migration. **Table 4** lists the *in situ* hydraulic conductivity, total porosity, and effective porosity for each compliance monitoring well to be used in these calculations.

### **5.3 Detection Monitoring Reporting**

The reporting of detection monitoring data will occur within 14 days from the completion of the statistical analysis of the ground-water quality analytical data. A report will be prepared which summarizes the sampling event, including field observations relating to the condition of the monitoring wells, field data, laboratory, statistical analysis, sampling methodologies, quality assurance and quality control data, information on ground-water flow direction, and calculations of ground-water flow rate.

### **5.4 Assessment Monitoring Program**

In the event that a statistically significant increase in concentration over background levels is detected in one or more of the constituents listed in Appendix I (Phase II monitoring) or a violation of the North Carolina ground-water quality standards (15A NCAC 2L, .0202) has occurred, the current landfill detection monitoring program will be switched to an assessment monitoring program (in accordance with 15A NCAC 13B, .1634) within 90 days of one of either of the two conditions stated above.

#### **5.4.1 Analytical Parameters and Sampling Frequency**

As part of this assessment monitoring program, all previous detection monitoring wells will be sampled in accordance with this plan and analyzed for all constituents identified in Appendix II of 40 CFR Part 258 "Appendix II List of Hazardous Inorganic and Organic Constituents

#### **5.4.2 Assessment Monitoring Reporting**

Once the ground-water quality results from the initial or subsequent assessment sampling event(s) has been collected, a "Notice of Detection" of Appendix II constituents will be submitted to the Division within 14 days. Once assessment monitoring has been initiated, sampling will be required at a minimum twice each year. One sampling event will be for all Appendix II constituents, and one sampling event will be for Appendix I constituents plus previously detected Appendix II constituents. A report of each sampling event will be developed and submitted to the Division for placement into the operating record.

Depending upon the constituent(s) detected, deletions to the Appendix II list may be requested if evidence can be provided to show that these constituents are not expected to be in or derived from the waste contained within the solid waste unit.

#### **5.4.3 Establishment and Reporting of Background Concentrations**

If any constituent listed in Appendix II is detected in a downgradient monitoring well, four independent sampling events will be performed on all program wells to establish new background levels for the newly detected constituents.

Once the background concentration for the detected Appendix II constituents has been determined, these concentrations will be reported to the Division to obtain a determination to establish ground-water protection standards for all detected parameters.

#### **5.4.4 Evaluation of Background and Assessment Data**

During the course of assessment monitoring, the evaluation of background and assessment data can lead to the execution of several options depending on the results of the statistical analysis of the sampling data. These options include:

1. If during the performance of assessment monitoring, compliance well concentrations for Appendix II constituents are at or below the determined background concentrations for two (2) consecutive sampling events, a request will be made to the Division to return to detection monitoring.
2. In the event that the concentration of detected Appendix II constituents is above the established background levels but are below the Division established ground-water protection standards, assessment monitoring will be continued until such time that conditions under option 1 are achieved.
3. If one or more of the detected Appendix II constituents are above the approved ground-water protection standards (in any sampling event), a report shall be submitted to the Division within 14 days of this finding and a notice placed in the operating record.

#### **5.5 Assessment of Corrective Measures**

In order to characterize the nature and extent of the release causing the detection of Appendix II constituents, additional ground water monitoring wells may be installed, as necessary. At least one additional well installed at the facility boundary in the hydraulically-downgradient direction of contaminant migration should be sampled in

accordance with the assessment monitoring program. Landowners downgradient of the release shall be notified in the event that off-site migration is expected.

Within 90 days of discovering statistically significant levels of Appendix II constituents over the approved ground-water protection standards, an assessment of corrective measures will be implemented in accordance with Rule 15A NCAC 13B, .1635.



## **APPENDIX I**

### Tables

**TABLE 1A**

**SUMMARY OF PROPOSED DETECTION MONITORING AND SAMPLING LOCATIONS**

**White Street Sanitary Landfill (Phase I)  
Greensboro, North Carolina**

SAMPLE ID NUMBER	SAMPLE TYPE	INTERVAL MONITORED	SAMPLE LOCATION AND POSITION		DETECTION MONITORING FUNCTION
			Distance and Direction From Waste Cell Boundary	Hydrogeologic Position	
I-1	Ground Water	Uppermost Aquifer	30 Feet West	Lateral	Provide Water Level and Quality Data
I-2	Ground Water	Uppermost Aquifer	5 Feet West	Lateral	Provide Water Level and Quality Data
I-3	Ground Water	Uppermost Aquifer	25 Feet West-Northwest	Downgradient	Provide Water Level and Quality Data
I-4	Ground Water	Uppermost Aquifer	25 Feet North	Downgradient	Provide Water Level and Quality Data
MW-13	Ground Water	Uppermost Aquifer	2,650 Feet Southwest	Upgradient	Provide Background Water Quality Data

All distances from waste cell boundary are approximates based on measurements taken from the scaled base map Drawing D-1.

**TABLE 1B**

**SUMMARY OF PROPOSED DETECTION MONITORING AND SAMPLING LOCATIONS**

**White Street Sanitary Landfill (Phase II)  
Greensboro, North Carolina**

SAMPLE ID NUMBER	SAMPLE TYPE	INTERVAL MONITORED	SAMPLE LOCATION AND POSITION		DETECTION MONITORING FUNCTION
			Distance and Direction From Waste Cell Boundary	Hydrogeologic Position	
II-1	Ground Water	Uppermost Aquifer	100 Feet Northwest	Downgradient	Provide Water Level and Quality Data
II-2	Ground Water	Uppermost Aquifer	75 Feet North	Downgradient	Provide Water Level and Quality Data
II-3	Ground Water	Uppermost Aquifer	100 Feet North	Downgradient	Provide Water Level and Quality Data
II-4	Ground Water	Uppermost Aquifer	50 Feet East-Northeast	Downgradient	Provide Water Level and Quality Data
II-5	Ground Water	Uppermost Aquifer	35 Feet East	Downgradient	Provide Water Level and Quality Data
II-6	Ground Water	Uppermost Aquifer	100 Feet West-Northwest	Downgradient	Provide Water Level and Quality Data
II-7	Ground Water	Uppermost Aquifer	75 Feet North	Downgradient	Provide Water Level and Quality Data
II-8	Ground Water	Uppermost Aquifer	100 Feet West	Downgradient	Provide Water Level and Quality Data

II-12	Ground Water	Uppermost Aquifer	100 Feet South-Southwest	Downgradient	Provide Water Level and Quality Data
MW-13	Ground Water	Uppermost Aquifer	4,350 Feet Southwest	Upgradient	Provide Background Water Quality Data
MW-14	Ground Water	Uppermost Aquifer	1,200 Feet South	Upgradient	Provide Background Water Quality Data
SW-2	Surface Water	Creek/Stream	3540 Feet West-Southwest	Not Applicable	Provide Downstream Surface Water Quality
SW-3	Surface Water	North Buffalo Creek	4000 Feet West-Southwest	Not Applicable	Provide Downstream WWTP Water Quality
SW-4	Surface Water	North Buffalo Creek	1350 Feet Northeast	Not Applicable	Provide Downstream Surface Water Quality
SW-5	Surface Water	North Buffalo Creek	250 Feet North	Not Applicable	Provide Downstream Surface Water Quality

All distances from waste cell boundary are approximates based on measurements taken from the scaled site map Drawing D-2.

**TABLE 2**

**SUMMARY OF SAMPLE PARAMETER MINIMUM QA/QC REQUIREMENTS**

**White Street Landfill  
Greensboro, North Carolina**

Parameter	Sampling Program	Container	Preservative	Volume	Holding Time
Antimony (Sb)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Arsenic (As)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Barium (Ba)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Beryllium (Be)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Cadmium (Cd)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Chromium (Cr)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Cobalt (Co)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Cyanide	Appendix II	plastic, glass	NaOH, pH >9	500 ml	14 days
Copper (Cu)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Lead (Pb)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Mercury (Hg)	Appendix II	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Nickel (Ni)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Selenium (Se)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Silver (Ag)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Sulfide	Appendix II	plastic, glass	H <sub>2</sub> SO <sub>4</sub> , pH <2	500 ml	7 days
Thallium (Tl)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Tin (Sn)	Appendix II	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Vanadium (Va)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
Zinc (Zn)	Appendix I	plastic, glass	HNO <sub>3</sub> , pH <2	100 ml	6 months
8240/8260 (VOC)	Appendix I/II	VOA	4° C	160 ml	14 days
8270 (Semi-VOC)	Appendix II	GA	4° C	1 liter	7/40 days
Chlor. Herbicides	Appendix II	GA	4° C	1 liter	7/40 days
Pesticides/PCBs	Appendix II	GA	4° C	1 liter	7/40 days
pH (std. units)	Appendix I/II	plastic, glass	4° C	100 ml	immediately
Specific Cond.	Appendix I/II	plastic, glass	4° C	100 ml	28 days

VOA - Volatile organic analysis vial (40 ml).

Plastic - Polyethylene bottle with a polypropylene cap.

GA - Glass amber bottle with Teflon® lined cap.

xx/xx days - days from extraction date/days for analysis after extraction.

HNO<sub>3</sub> - Nitric acid.

H<sub>2</sub>SO<sub>4</sub> - Sulfuric acid.

NaOH - Sodium hydroxide.

8240/8260 - SW-846 GC/MS Method.

<b>TABLE 3A</b>  <b>SUMMARY OF WATER QUALITY ANALYTICAL SAMPLE PARAMETERS</b>  White Street Landfill (Phase I) White Street Greensboro, North Carolina			
Metals:			
PARAMETER	CERTIFICATION	METHOD	SWSL
Arsenic	low level	6010B	10
Barium	low level	6010B	100
Cadmium	low level	6010B	1
Chromium	low level	6010B	10
Lead	low level	6010B	10
Mercury	low level	7470A	0.2
Selenium	low level	6010B	10
Silver	low level	6010B	10
SWSL – Solid Waste Section Limit in parts per billion (ppb).			

Volatile Organic:		
ORGANIC CONSTITUENT	METHOD	SWSL
Acetone	8240/8260	100
Acrylonitrile	8240/8260	55
Benzene	8240/8260	1
Bromochloromethane	8240/8260	3
Bromodichloromethane	8240/8260	1
Bromoform	8240/8260	3
Carbon Disulfide	8240/8260	100
Carbon Tetrachloride	8240/8260	1
Chlorobenzene	8240/8260	3
Chloroethane	8240/8260	10
Chlorodibromomethane	8240/8260	3

**TABLE 3a (continuation)**  
**SUMMARY OF WATER QUALITY ANALYTICAL SAMPLE PARAMETERS**

White Street Landfill (Phase I)  
 White Street  
 Greensboro, North Carolina

Volatile Organic:

ORGANIC CONSTITUENT	METHOD	SWSL
Chloroform	8240/8260	5
1,2-Dibromo-3-Chloropropane	8240/8260	13
Ethylene Dibromide	8240/8260	1
O-Dichlorobenzene	8240/8260	5
P-Dichlorobenzene	8240/8260	1
T-1,4-Dichloro-2-Butene	8240/8260	100
1,1-Dichloroethane	8240/8260	1
1,2-Dichloroethane	8240/8260	1
1,1-Dichloroethene	8240/8260	1
Cis-1,2-Dichloroethene	8240/8260	5
T-1,2-Dichloroethene	8240/8260	5
1,2-Dichloropropane	8240/8260	1
Cis-1,3-Dichloropropene	8240/8260	1
T-1,3-Dichloropropene	8240/8260	1
Ethylbenzene	8240/8260	1
Methyl Butyl Ketone	8240/8260	50
Methyl Bromide	8240/8260	10
Methyl Chloride	8240/8260	1
Methylene Bromide	8240/8260	10
Methylene Chloride	8240/8260	1
MEK; 2-Butanone	8240/8260	100
Methyl Iodide	8240/8260	10
Methyl Isobutyl Ketone	8240/8260	100

SWSL – Solid Waste Section in parts per billion (ppb).

**TABLE 3a (continuation)**  
**SUMMARY OF WATER QUALITY ANALYTICAL SAMPLE PARAMETERS**

White Street Landfill (Phase I)  
 White Street  
 Greensboro, North Carolina

**Volatile Organic:**

<b>ORGANIC CONSTITUENT</b>	<b>METHOD</b>	<b>SWSL</b>
Styrene	8240/8260	1
1,1,1,2-Tetrachloroethane	8240/8260	5
1,1,2,2-Tetrachloroethane	8240/8260	3
Tetrachloroethylene	8240/8260	1
Toluene	8240/8260	1
1,1,1-Trichloroethane	8240/8260	1
1,1,2-Trichloroethane	8240/8260	1
Trichloroethylene	8240/8260	1
Trichlorofluoromethane	8240/8260	1
1,2,3-Trichloropropane	8240/8260	1
Vinyl Acetate	8240/8260	50
Vinyl Chloride	8240/8260	1
Xylenes	8240/8260	5

SWSL – Solid Waste Section Limit in micrograms per liter (ug/l).

**Water Quality Field Measurements:**

<b>PARAMETER</b>	<b>METHOD</b>	<b>SWSL</b>
Temperature	Field Thermometer or equivalent	NE
Specific Conductance	Field-Calibrated Meter	NE
pH	Field-Calibrated Meter	NE



**TABLE 3B**

**SUMMARY OF GROUND-WATER QUALITY ANALYTICAL  
PARAMETERS**

**White Street Sanitary Landfill (Phase II)  
Greensboro, North Carolina**

**Metals:**

PARAMETER	CERTIFICATION	METHOD	SWSL
Antimony	Low Level	6020B	6
Arsenic	Low Level	6010B	10
Barium	Low Level	6010B	100
Beryllium	Low Level	6010B	1
Cadmium	Low Level	6010B	1
Chromium	Low Level	6010B	10
Cobalt	Low Level	6010B	10
Copper	Low Level	6010B	10
Lead	Low Level	6010B	10
Mercury	Low Level	7470A	0.2
Nickel	Low Level	6010B	50
Selenium	Low Level	6010B	10
Silver	Low Level	6010B	10
Thallium	Low Level	6020B	5.5
Tin	Low Level	6010B	100
Vanadium	Low Level	6010B	25
Zinc	Low Level	6010B	10

SWSL – Solid Waste Section Limit in parts per billion (ppb).

**TABLE 3b (continuation)**

**SUMMARY OF GROUND-WATER QUALITY ANALYTICAL  
 PARAMETERS**

**White Street Sanitary Landfill (Phase II)  
 Greensboro, North Carolina**

**Volatile Organics:**

<b>ORGANIC CONSTITUENT</b>	<b>METHOD</b>	<b>SWSL</b>
Acetone	8240/8260	100
Acrylonitrile	8240/8260	55
Benzene	8240/8260	1
Bromochloromethane	8240/8260	3
Bromodichloromethane	8240/8260	1
Bromoform	8240/8260	3
Carbon Disulfide	8240/8260	100
Carbon Tetrachloride	8240/8260	1
Chlorobenzene	8240/8260	3
Chloroethane	8240/8260	10
Chloroform	8240/8260	5
Chlorodibromomethane	8240/8260	3
1,2-Dibromo-3-Chloropropane	8240/8260	13
Ethylene Dibromide	8240/8260	1
O-Dichlorobenzene	8240/8260	5
P-Dichlorobenzene	8240/8260	1
T-1,4-Dichloro-2-Butene	8240/8260	100
1,1-Dichloroethane	8240/8260	5
1,2-Dichloroethane	8240/8260	1
1,1-Dichloroethene	8240/8260	5
Cis-1,2-Dichloroethene	8240/8260	5

SWSL – Solid Waste Section Limit in micrograms per liter (ug/l).

**TABLE 3b (continuation)**

**SUMMARY OF GROUND-WATER QUALITY ANALYTICAL  
 PARAMETERS**

**White Street Sanitary Landfill (Phase II)  
 Greensboro, North Carolina**

**Volatile Organics:**

<b>ORGANIC CONSTITUENT</b>	<b>METHOD</b>	<b>SWSL</b>
T-1,2-Dichloroethene	8240/8260	5
1,2-Dichloropropane	8240/8260	1
Cis-1,3-Dichloropropene	8240/8260	1
T-1,3-Dichloropropene	8240/8260	1
Ethylbenzene	8240/8260	1
Methyl Butyl Ketone	8240/8260	50
Methyl Bromide	8240/8260	10
Methyl Chloride	8240/8260	1
Methylene Bromide	8240/8260	10
Methylene Chloride	8240/8260	1
MEK; 2-Butanone	8240/8260	100
Methyl Iodide	8240/8260	10
Methyl Isobutyl Ketone	8240/8260	100
Styrene	8240/8260	10
1,1,1,2-Tetrachloroethane	8240/8260	5
1,1,2,2-Tetrachloroethane	8240/8260	3
Tetrachloroethylene	8240/8260	1
Toluene	8240/8260	1
1,1,1-Trichloroethane	8240/8260	1
1,1,2-Trichloroethane	8240/8260	1
Trichloroethylene	8240/8260	1

SWSL – Solid Waste Section Limit in micrograms per liter (ug/l).

**TABLE 3b (continuation)**

**SUMMARY OF GROUND-WATER QUALITY ANALYTICAL  
PARAMETERS**

**White Street Sanitary Landfill (Phase II)  
Greensboro, North Carolina**

**Volatile Organics:**

<b>ORGANIC CONSTITUENT</b>	<b>METHOD</b>	<b>SWSL</b>
Trichlorofluoromethane	8240/8260	1
1,2,3-Trichloropropane	8240/8260	1
Vinyl Acetate	8240/8260	50
Vinyl Chloride	8240/8260	1
Xylenes	8240/8260	5

SWSL – Solid Waste Section Limit in micrograms per liter (ug/l).

**Water Quality Field Measurements:**

<b>PARAMETER</b>	<b>METHOD</b>	<b>SWSL</b>
Temperature	Field Thermometer or equivalent	0.1 °c
Specific Conductance	Field-Calibrated Meter	1.0 umhos/cm <sup>3</sup>
pH	Field-Calibrated Meter	0.01 su

**TABLE 4**

**SUMMARY OF DETECTION MONITORING WELL  
HYDROGEOLOGIC PARAMETERS**

**White Street Landfill**  
Greensboro, North Carolina

Well #	Hydraulic Conductivity		Estimated Porosity, %	
	cm/sec	ft/day	Total <sup>3</sup>	Effective <sup>4</sup>
II-1 <sup>1</sup>	$4.21 \times 10^{-5}$	0.119	35-50	15
II-2 <sup>1</sup>	$1.16 \times 10^{-4}$	0.329	35-50	15
II-3 <sup>1</sup>	$1.34 \times 10^{-4}$	0.380	35-50	15
II-4 <sup>1</sup>	$7.06 \times 10^{-5}$	0.200	35-50	15
II-5 <sup>1</sup>	$1.49 \times 10^{-5}$	0.042	35-50	15
II-6 <sup>2</sup>	$7.8 \times 10^{-5}$	0.221	35-50	15
II-7 <sup>2</sup>	$3.8 \times 10^{-4}$	1.077	35-50	15
II-8 <sup>2</sup>	$8.3 \times 10^{-4}$	2.353	35-50	15
MW-13 <sup>1</sup>	$5.00 \times 10^{-5}$	0.142	35-50	15
MW-14 <sup>2</sup>	$2.61 \times 10^{-4}$	0.740	35-50	15

<sup>1</sup> Hydraulic conductivity values provided by BPA Environmental & Engineering, Inc. Data analyzed using method of Hvorslev, M.J., Time Lag and Soil Permeability in Groundwater Observations, US Army Corps of Engineers Waterways Experimental Station, Bulletin 36, 1951.



<sup>2</sup> Hydraulic conductivity values provided by HDR Engineering, Inc. Data analyzed using method of Bouwer, H. and Rice, R.C., 1976, A Slug Test for Determining Hydraulic Conductivity of Unconfined Aquifers with Completely or Partially Penetrating Wells, Water Resources Research, v. 12, pp. 423-428.

<sup>3</sup> Total porosity values estimated from undisturbed samples taken elsewhere at the White Street Landfill. These are a typical range of values for the sandy silts to silty sands found at the site.



<sup>4</sup> Estimated effective porosity values are from Table 3-1 in the "Interim Final Guidance Document on the Statistical Analysis of Ground-Water Monitoring Data at RCRA Facilities," USEPA, April 1989. Based on boring logs, although some silty sands were present, sandy silt soil was chosen as the typical and more conservative texture for the aquifer at each detection monitoring well.

## **APPENDIX II**

### Sample Location Maps




- LEGEND:**
- ◆ MONITORING WELL LOCATION
  - OFF-SITE PROPERTY OWNED BY THE CITY OF GREENSBORO
  - ✦ AUGER REFUSAL AT 6.5 FT. TO 10 FT. BELOW GRADE



**PHASE I and II  
GROUNDWATER SAMPLING PLAN  
WHITE STREET LANDFILL  
GREENSBORO, NORTH CAROLINA**


CHECKED BY: CDW
FIGURE NO. 1
DRAWN BY: DSB/RDM
DATE: DECEMBER 2007
SCALE: AS SHOWN
JOB NO. 1584-98-081





**PHASE I and II  
SURFACE WATER SAMPLING LOCATIONS  
WHITE STREET LANDFILL  
GREENSBORO, NORTH CAROLINA**

SCALE: AS SHOWN	DRAWN BY: DSB/RDM	CHECKED BY: LE
JOB NO. 1584-98-081	DATE: DECEMBER 2007	FIGURE NO. 2





## **APPENDIX III**

### Soil Boring Logs and Well Construction Records

OWNER City of Greensboro				BORING NUMBER 8-1									
PROJECT NAME Greensboro Landfill				ARCHITECT-ENGINEER									
SITE LOCATION Greensboro, NC			JOB NO. 88-387-E		UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup>								
DEPTH IN FEET	SAMPLE NO.	SAMPLE TYPE	SAMPLE DEPTH FROM TO	DESCRIPTION OF MATERIAL	PLASTIC LIMIT %			WATER CONTENTS %			LIQUID LIMIT %		
					1	2	3	4	5	1	2	3	4
SURFACE ELEVATION 6" Topsoil					STANDARD PENETRATION 10 20 30 40 50								
5	1	ss	2.5 4.0	SILTY SAND, tan, white, stiff, (SM-ML). NOTE: Residual Soil/Saprolite.	35								
	2	ss	5.0 6.5	SILTY SAND, tan, white, v/stiff, (SM-ML). NOTE: Saprolite/weathered rock, coarse to fine grained sand.	40								
	3	ss	7.5 9.0		50								
10	4	ss	10.0 11.5	V/hard. NOTE: Weathered rock consisting predominately of sand to gravel-size frags. consisting of quartz feldspar and mica, obvious parent rock of above soils.	Well Screen Set At 14-24 ft.								
15	5	ss	15.0 16.5										
20	6	ss	20.0 21.5	Auger Refusal at 24.0'									
25													
30													

## WELL COMPLETION RECORD

AE OF SITE:

PERMIT NO.:

Well No. 1

OWNER (print):

City Of Greensboro

REGISTRATION NO.:

835.


Water Level: \_\_\_\_\_ feet from top of casing

Date Measured \_\_\_\_/\_\_\_\_/\_\_\_\_

DRILLING LOG		
DEPTH		FORMATION DESCRIPTION
FROM	TO	

### LOCATION SKETCH

(show distance to numbered roads, or other map reference points)



REMARKS:

DATE: 7-14-89

SIGNATURE:

OWNER City of Greensboro				BORING NUMBER B-2					
PROJECT NAME Greensboro Landfill				ARCHITECT-ENGINEER I-2					
SITE LOCATION Greensboro, NC				JOB. NO. 88-387-E		UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup>			
DEPTH IN FEET	SAMPLE NO.	SAMPLE TYPE	SAMPLE DEPTH FROM-TO	DESCRIPTION OF MATERIAL	1 2 3 4 5 PLASTIC LIMIT % WATER CONTENTS % LIQUID LIMIT % X ⊕ Δ 10 20 30 40 50				
					STANDARD PENETRATION BLOWS/FT. 10 20 30 40 50				
				SURFACE ELEVATION					
5	1	ss	2.5 4.0	CLAYEY SILT, w/little gravel, brown, black, gray, red, soft, (ML-CL). NOTE: Residual soil with abundant organics (roots, stems, grass, etc.)	9				
	2	ss	5.0 6.5		7				
	3	ss	7.5 9.0	CLAY, w/little sand, gray, tan, firm, (CL-CH). NOTE: Residual Soil/Saprolite.	12				
10	4	ss	10.0 11.5		11				
15	5	ss	15.0 16.5	SANDY CALY, gray, red, tan, soft, (CL-CH). NOTE: Residual Soil/Saprolite.	8				
20	6	ss	20.0 21.5	SANDY SILT, green, gray, v/hard, (ML). NOTE: Residual Soil/Saprolite.					
25				Auger Refusal at 22'.					
30									

Well Screen Set At 12-22 ft.

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES. IN-SITU, THE TRANSITION MAY BE GRADUAL

WATER TABLE DATA — DEPTH BELOW SURFACE 16.0' (BAR) ● 0 HRS.		BORING STARTED 5-11-89		BORING COMPLETED 5-11-89	
● HRS.		RIG B-50	FOREMAN R. Barron	APP'D BY ABN	AUGER 6" HSA

ENGINEERING TECTONICS, P. A.

## WELL COMPLETION RECORD

AGE OF SITE:

PERMIT NO.:

Well No. 2

OWNER (print):

City Of Greensboro

REGISTRATION NO.:

835

Static Water Level: \_\_\_\_\_ feet from top of casing

Date Measured \_\_\_\_ / \_\_\_\_ / \_\_\_\_


# DRILLING LOG

DEPTH

FROM	TO	FORMATION DESCRIPTION
1	2	3
4	5	6
7	8	9
10	11	12
13	14	15
16	17	18
19	20	21
22	23	24
25	26	27
28	29	30
31	32	33
34	35	36
37	38	39
40	41	42
43	44	45
46	47	48
49	50	51
52	53	54
55	56	57
58	59	60
61	62	63
64	65	66
67	68	69
70	71	72
73	74	75
76	77	78
79	80	81
82	83	84
85	86	87
88	89	90
91	92	93
94	95	96
97	98	99
100	101	102
103	104	105
106	107	108
109	110	111
112	113	114
115	116	117
118	119	120
121	122	123
124	125	126
127	128	129
130	131	132
133	134	135
136	137	138
139	140	141
142	143	144
145	146	147
148	149	150
151	152	153
154	155	156
157	158	159
160	161	162
163	164	165
166	167	168
169	170	171
172	173	174
175	176	177
178	179	180
181	182	183
184	185	186
187	188	189
190	191	192
193	194	195
196	197	198
199	200	201
202	203	204
205	206	207
208	209	210
211	212	213
214	215	216
217	218	219
220	221	222
223	224	225
226	227	228
229	230	231
232	233	234
235	236	237
238	239	240
241	242	243
244	245	246
247	248	249
250	251	252
253	254	255
256	257	258
259	260	261
262	263	264
265	266	267
268	269	270
271	272	273
274	275	276
277	278	279
280	281	282
283	284	285
286	287	288
289	290	291
292	293	294
295	296	297
298	299	300
301	302	303
304	305	306
307	308	309
310	311	312
313	314	315
316	317	318
319	320	321
322	323	324
325	326	327
328	329	330
331	332	333
334	335	336
337	338	339
340	341	342
343	344	345
346	347	348
349	350	351
352	353	354
355	356	357
358	359	360
361	362	363
364	365	366
367		

See Attached Boring log

(show distance to numbered roads, or other map reference points)



REMARKS:

DATE: 7-14-89

SIGNATURE:

OWNER City of Greensboro				BORING NUMBER B-4			
PROJECT NAME Greensboro Landfill				ARCHITECT-ENGINEER I-3			
SITE LOCATION Greensboro, NC				JOB. NO. 88-387-E			

DEPTH IN FEET	SAMPLE NO.	SAMPLE TYPE	SAMPLE DEPTH FROM TO	DESCRIPTION OF MATERIAL	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup>			WATER CONTENTS %			LIQUID LIMIT %			STANDARD PENETRATION BLOWS/FT.				
					1	2	3	4	5	10	20	30	40	50	10	20	30	40
5	1	SS	2.5 4.0	SANDY CLAY, brown, black, soft, (CL). NOTE: Alluvial/fill?														
	2	SS	5.0 6.5	SILTY CLAY, brown, gray, tan, soft, (CL). NOTE: Alluvial/fill?														
	3	SS	7.5 9.0	SILTY SAND, gray, red, soft, (SM). NOTE: Residual Soil/Saprolite, fine-grained well sorted sand														
	4	SS	10.0 11.5	GRAVELLY SAND, black, tan, white, (SP). NOTE: Saprolite/weathered rock consisting of quartz, feldspar, mica and mafic mineral, abundant sand to gravel size rock frags.														
	5	SS	15.0 16.5	CLAYEY GRAVELLY SILT, brown, gray, tan, v/hard, (SC). NOTE: Saprolite/weathered rock with abundant sand to gravel size rock frags.														
				Boring Terminated at 16.0'.														

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU. THE TRANSITION MAY BE GRADUAL

WATER TABLE DATA — DEPTH BELOW SURFACE 6.0' (BAR) ● 0 HRS.		BORING STARTED RIG B-50		FOREMAN R. Barron		BORING COMPLETED APP'D BY ABN		AUGER 6" HSA	
---	--	----------------------------	--	-------------------	--	----------------------------------	--	--------------	--

ENGINEERING TECTONICS, P. A.

## WELL COMPLETION RECORD

NAME OF SITE:

PERMIT NO.:

Well No. 4

OWNER (print):

City Of Greensboro

REGISTRATION NO.:

835


Static Water Level: \_\_\_\_\_ feet from top of casing

Date Measured \_\_\_\_ / \_\_\_\_ / \_\_\_\_

[illegible]

LOCATION SKETCH

(show distance to numbered roads, or other map reference points)



REMARKS:

DATE: 7-14-89 SIGNATURE: \_\_\_\_\_





## WELL COMPLETION RECORD

NAME OF SITE:

PERMIT NO.:

Well No. 5

ADDRESS:

OWNER (print):

Off White Street in Greensboro, NC

City Of Greensboro

BILLING CONTRACTOR:

REGISTRATION NO.:

Engineering Tectonics, P.A.

835

ing Type: Sch 40 PVC dia. 2 in. Grout Depth: from 0 to 11 ft. - dia. 6 in.  
ing Depth: from 0 to 14 ft. - dia. 2 in. Bentonite Seal: from 11 to 12 ft. - dia. 6 in.  
en Type: PVC .010 Slot dia. 2 in. Sand/Gravel PK: from 12 to 24 ft. - dia. 6 in.  
en Depth: from 14 to 24 ft. - dia. 2 in. Total Well Depth: from 0 to 24 ft. - dia. 6 in.

Date Measured \_\_\_\_/\_\_\_\_/\_\_\_\_

and (gpm): \_\_\_\_\_ Method of Testing: \_\_\_\_\_ Casing is \_\_\_\_\_ feet above land surface

## DRILLING LOG


DEPTH

FROM	TO	FORMATION DESCRIPTION
1	2	3
4	5	6
7	8	9
10	11	12
13	14	15
16	17	18
19	20	21
22	23	24
25	26	27
28	29	30
31	32	33
34	35	36
37	38	39
40	41	42
43	44	45
46	47	48
49	50	51
52	53	54
55	56	57
58	59	60
61	62	63
64	65	66
67	68	69
70	71	72
73	74	75
76	77	78
79	80	81
82	83	84
85	86	87
88	89	90
91	92	93
94	95	96
97	98	99
100	101	102
103	104	105
106	107	108
109	110	111
112	113	114
115	116	117
118	119	120
121	122	123
124	125	126
127	128	129
130	131	132
133	134	135
136	137	138
139	140	141
142	143	144
145	146	147
148	149	150
151	152	153
154	155	156
157	158	159
160	161	162
163	164	165
166	167	168
169	170	171
172	173	174
175	176	177
178	179	180
181	182	183
184	185	186
187	188	189
190	191	192
193	194	195
196	197	198
199	200	201
202	203	204
205	206	207
208	209	210
211	212	213
214	215	216
217	218	219
220	221	222
223	224	225
226	227	228
229	230	231
232	233	234
235	236	237
238	239	240
241	242	243
244	245	246
247	248	249
250	251	252
253	254	255
256	257	258
259	260	261
262	263	264
265	266	267
268	269	270
271	272	273
274	275	276
277	278	279
280	281	282
283	284	285
286	287	288
289	290	291
292	293	294
295	296	297
298	299	300
301	302	303
304	305	306
307	308	309
310	311	312
313	314	315
316	317	318
319	320	321
322	323	324
325	326	327
328	329	330
331	332	333
334	335	336
337	338	339
340	341	342
343	344	345
346	347	348
349	350	351
352	353	354
355	356	357
358	359	360
361	362	363
364	365	366
367		

See Attached Boring Log

### LOCATION SKETCH

(show distance to numbered roads, or other map reference points)



REMARKS:

DATE: 7-14-89

SIGNATURE:

OWNER City of Greensboro				BORING NUMBER B-7			
PROJECT NAME Greensboro Landfill				ARCHITECT-ENGINEER JL			
SITE LOCATION Greensboro, NC				JOB. NO. 88-387-E			

DEPTH IN FEET	SAMPLE NO.	SAMPLE TYPE	SAMPLE DEPTH FROM TO	DESCRIPTION OF MATERIAL	UNCONFINED COMPRESSIVE STRENGTH TONS/FT. <sup>2</sup>		
					1	2	3
					PLASTIC LIMIT %      WATER CONTENTS %      LIQUID LIMIT % X                                  ⊕                                  Δ 10                                  20                                  30                                  40                                  50		
					STANDARD PENETRATION      BLOWS/FT. 10                                  20                                  30                                  40                                  50		
5	1	ss	2.5 4.0	SILT, w/little clay, reddish-brown, firm, (ML). NOTE: Trace organics (fine roots) with an occasional gravel size rock frag., fill.	17		
	2	ss	5.0 6.5		14		
	3	ss	7.5 9.0		9		
10	4	ss	10.0 11.5		15		
15	5	ss	15.0 16.5	SILTY CLAY, w/trace sand, gray, tan, soft to firm, (CL-ML). NOTE: Residual Soil/Alluvial?	7		
20	6	ss	20.0 21.5		10		
25	7	ss	25.0 26.5	SANDY SILT, w/little gravel, gray, v/stiff to v/hard, (ML-SM). NOTE: Saprolite/weathered rock with granitic and quartz gravel size rock fragments.			
30	8	ss	30.0 31.5	Boring Terminated at 30'.			

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES: IN-SITU. THE TRANSITION MAY BE GRADUAL

WATER TABLE DATA — DEPTH BELOW SURFACE	BORING STARTED      6-13-89	BORING COMPLETED      6-13-89
--      ● 0 HRS. 18.34'      ● Below TOC HRS.	RIG B-50      FOREMAN R. Barron	APP'D BY ABN      AUGER 6" HSA
7-12-89		

ENGINEERING TECTONICS, P. A.

## WELL COMPLETION RECORD

FORM TO THE N.C.  
CENT BRANCH.

Casing Type: Sch 40 PVC dia. 2 in. Grout Depth: from 0 to 17 ft. - dia. 6 in.  
 Casing Depth: from 0 to 20 ft. - dia. 2 in. Bentonite Seal: from 17 to 18 ft. - dia. 6 in.  
 Screen Type: PVC .010 Slot dia. 2 in. Sand/Gravel PK: from 18 to 30 ft. - dia. 6 in.  
 Screen Depth: from 20 to 30 ft. - dia. 2 in. Total Well Depth: from 0 to 30 ft. - dia. 6 in.

Static Water Level: 18.34 feet from top of casing Date Measured 7 / 12 / 89

Yield (gpm): low Method of Testing: Bail Casing is 3.83 feet above land surface

### LOCATION SKETCH

(show distance to numbered roads, or other map reference points)

The map shows the site location in Greensboro, North Carolina. The site is marked with a black dot in the upper right quadrant. Major roads shown include I-40 (top), I-77 (right), and US-1 (bottom). Local streets shown include Market St, Elm St, Pine St, and others. Key landmarks include Battleground Park, Latham Park, and Wendover. The map also shows the location of the site relative to the city center and other major roads.

REMARKS:

ATE: 7-14-89

SIGNATURE:



## WELL COMPLETION RECORD

COMPLETE ALL INFORMATION REQUESTED BELOW FOR EACH WELL INSTALLED, AND RETURN FORM TO THE N.C. DEPARTMENT OF HUMAN RESOURCES, SOLID AND HAZARDOUS WASTE MANAGEMENT BRANCH, P.O. BOX 2091, RALEIGH, N.C. 27602

NAME OF SITE: Greensboro Landfill		PERMIT NO.: Well No. 8
ADDRESS: Off White Street in Greensboro, NC		OWNER (print): City Of Greensboro
DRILLING CONTRACTOR: Engineering Tectonics, P.A.		REGISTRATION NO.: 835

Drilling Type: Sch 40 PVC dia. 2 in. Grout Depth: from 0 to 17 ft. - dia. 6 in.  
Drilling Depth: from 0 to 20 ft. - dia. 2 in. Bentonite Seal: from 17 to 18 ft. - dia. 6 in.  
Casing Type: PVC .010 Slot dia. 2 in. Sand/Gravel PK: from 18 to 30 ft. - dia. 6 in.  
Casing Depth: from 20 to 30 ft. - dia. 2 in. Total Well Depth: from 0 to 30 ft. - dia. 6 in.

Static Water Level: 16.63 feet from top of casing Date Measured 7 / 12 / 89  
Flow (gpm): 10W Method of Testing: Bail Casing is 3.13 feet above land surface


### DRILLING LOG

DEPTH	FORMATION DESCRIPTION
-------	-----------------------

See Attached Boring Log

### LOCATION SKETCH

(show distance to numbered roads, or other map reference points)



SIGNATURE: \_\_\_\_\_




## WELL COMPLETION RECORD

NAME OF SITE: Greensboro Landfill		PERMIT NO.: Well No. 9
ADDRESS: Off White Street in Greensboro, NC		OWNER (print): City Of Greensboro
INSTALLING CONTRACTOR: Engineering Tectonics, P.A.		REGISTRATION NO.: 835

Pipe Type: SCH 40 PVC dia. 2 in. Grout Depth: from 0 to 13 ft. - dia. 6 in.  
 Pipe Depth: from 0 to 16 ft. - dia. 2 in. Bentonite Seal: from 13 to 14 ft. - dia. 6 in.  
 Screen Type: PVC .010 Slot dia. 2 in. Sand/Gravel PK: from 14 to 26 ft. - dia. 6 in.  
 Screen Depth: from 16 to 26 ft. - dia. 2 in. Total Well Depth: from 0 to 26 ft. - dia. 6 in.

Static Water Level: 13.16 feet from top of casing Date Measured 7/12/89

Discharge (gpm): LOW Method of Testing: Bail Casing is 3.42 feet above land surface

[illegible]

FMARKS: \_\_\_\_\_

DATE: 7-14-89 SIGNATURE: \_\_\_\_\_

# WELL CONSTRUCTION RECORD

MW-II-6

FOR OFFICE USE ONLY			
Quad No.	Serial No.		
Lat.	Long.	Pc	
Minor Basin	Basin Code		
Header Ent.	GW-1 Ent.		

DRILLING CONTRACTOR: BADGER DRILLING

DRILLER REGISTRATION NUMBER: 1486

STATE WELL CONSTRUCTION PERMIT NUMBER:

1. WELL LOCATION: (Show sketch of the location below)  
Nearest Town: COLUMBIANA NC

(Road, Community, or Subdivision and Lot No.)

County:

Depth From To

Drilling Log Formation Description

2. OWNER:

ADDRESS:

Street or Route No.

City or Town

State

Zip Code

3. DATE DRILLED: 9-12-94

USE OF WELL: WATER SUPPLY

4. TOTAL DEPTH: 17.0

CUTTINGS COLLECTED: ☒ Yes ☐ No

5. DOES WELL REPLACE EXISTING WELL? ☐ Yes ☒ No

6. STATIC WATER LEVEL:

FT. Above Below

TOP OF CASING,

TOP OF CASING IS: 2.5 FT. ABOVE LAND SURFACE.

7. YIELD (gpm): N/A

METHOD OF TEST: AIR

8. WATER ZONES (depths): N/A

9. CHLORINATION: Type N/A Amount

10. CASING:

If additional space is needed use back of form.

LOCATION SKETCH

(Show direction and distance from at least two State Roads, or other map reference points).

11. GROUT:

From 0.0 To 3.0 Ft.

Depth 3.0 Ft.

Diameter 2"

Material PORTLAND CEMENT

Method

12. SCREEN:

From 4.5 To 17.0 Ft.

Depth 17.0 Ft.

Diameter 2"

Slot Size 10/10 in.

Material PVC

13. GRAVEL PACK:

From 3.0 To 17.0 Ft.


Depth 17.0 Ft.

# 2 Size

Material

14. REMARKS:

REINFORCE SEAL 10' TO 3.0'



I DO HEREBY CERTIFY THAT THIS WELL WAS CONSTRUCTED IN ACCORDANCE WITH 15 NCAC 2C WELL CONSTRUCTION STANDARDS, AND THAT A COPY OF THIS RECORD HAS BEEN PROVIDED TO THE WELL OWNER.

SIGNATURE OF CONTRACTOR OR AGENT


9-12-94

DATE



# MONITORING WELL INSTALLATION DIAGRAM

PEIZOMETER NO.: MW-II-6  
BORING NO.: B-II-6  
JOB NO.: 6770-00 -018  
PREPARED BY: C. LEE  
CHECKED BY: C. LEE  
DATE: \_\_\_\_\_



## HDR

HDR Engineering, Inc.

REMARKS: ALL MEASUREMENTS TO THE NEAREST 0.1 FT.

PROJECT: WHITE STREET LANDFILL

PROJECT NO: 6770-0 -018

LOCATION: GREENSBORO, N.C.

BORING NUMBER: II-6  
OFFSET 10' SOUTH

PAGE: 1

## BORING LOG

DATE: 9/12/94

NUMBER	DEPTH	SPT	T	WL	SI	DESCRIPTION (USCS)	COMMENTS
	4'					RED ORANGE SL. SANDY CLAYEY SILT	AMPHIBOLITE  WILL MOVE 10' SOUTH/TRY AGAIN
	8'					GREEN-GREY SILT	
	12'					DK. GREEN/TAN SPECKLED, POORLY FOLIATED SL. SANDY SILT, BLACK STREAKS ON FRACTURES, HARD	
SS-3	16'	50/6"	SS				
	20'					EOH @ 18.0'	
	24'						
	28'						
	32'						
	36'						
	40'						

BOREHOLE COMPLETION: 18.0' BELOW GROUND

WATER DEPTH: ~ 6.0'

DATE: 9/12/94

DRILLING METHOD: HOLLOW STEM AUGERS

LOGGED BY: HDR ENGINEERING, INC.

## KEY:

SI - SCREEN  
SS - SPLITSPOON  
SPT - SOIL PENETRATION  
TEST-N NUMBER  
ST - SHELBY TUBE  
T - TYPE  
WL - WATER LEVEL**HDR**

PROJECT: WHITE STREET LANDFILL

PROJECT NO: 6770-0 -018

LOCATION: GREENSBORO, N.C.

BORING NUMBER: II-6

PAGE: 1

## BORING LOG

DATE: 9/12/94

NUMBER	DEPTH	SPT	T	WL	SI	DESCRIPTION (USCS)	COMMENTS
	4'						
SS-1		23-23 15-18	SS			RED, BROWN LAMINATED CLAYEY SILT TO 5.5. THEN LT. GREEN GREY SILT. HARD FINELY LAMINATED	
	8'						
SS-2		8-17 20-26	SS			GREY GREEN, BROWN STREAKED FOLIATED SILT TO DK GREY V. FINE SILT W/WHITE STREAKS. PWR.	AMPHIBOLITE
	12'					ROCK @ ~13'-0" AUGER REFUSAL	WILL MOVE 10' SOUTH/TRY AGAIN
	20'						
	24'						
	28'						
	32'						
	36'						
	40'						

BOREHOLE COMPLETION: 13.0' BELOW GROUND

WATER DEPTH: @ 2:30 WL @ 10.5' BELOW GRADE DATE: 9/12/94

DRILLING METHOD: HOLLOW STEM AUGERS

LOGGED BY: HDR ENGINEERING, INC.

## KEY:

SI - SCREEN  
 SS - SPLITSPOON  
 SPT - SOIL PENETRATION  
 TEST-N NUMBER  
 ST - SHELBY TUBE  
 T - TYPE  
 WL - WATER LEVEL



PROJECT: WHITE STREET LANDFILL

PROJECT NO: 6770-0 -018

LOCATION: GREENSBORO, N.C.

BORING NUMBER: II-7

PAGE: 1

## BORING LOG

DATE: 9/12/94

NUMBER	DEPTH	SPT	T	WL	SI	DESCRIPTION (USCS)	COMMENTS
	4'						
SS-1		3-3 4-4	SS			RED BROWN SILTY CLAY, W/BLACK WHITE AMPHIBOLITE PEBBLE IN TIP	
	8'						
SS-2	12'	5-5 7-8	SS			BROWN FINELY LAMINATED CLAYEY, SL. SANDY SILT TO GREEN-ORANGE SPOTTED CRUDELY FOL WEATHERED SILT	SCHIST./ AMPHIBOLITE
SS-3	16'	7-8 19-23	SS			DK GREEN/PALE TAN SPECKLED M-C S. SILT W/FeOx FRACTURES AT BASE, 1.0 GREEN/BROWN FINELY LAM. SILT AT TOP OF INTERVAL	SCHIST./ AMPHIBOLITE
	20'						
SS-4		13-13 26-22	SS			GREEN/BROWN EQUIGRAN SL. SANDY SILT TO LAMINATED/FOLIATED PURPLISH BRN & GREEN SL. SANDY SILT TO GREEN/TAN EQUIGRAN SL. SANDY SILT	GETTING HARD ALT FOL. SCHIST AMPHIBOLITE
	24'						
	28'					EOH @ 25.0'	
	32'						
	36'						
	40'						

BOREHOLE COMPLETION: 25.0'

WATER DEPTH: ~ 12.0'

DATE: 9/12/94

DRILLING METHOD: HOLLOW STEM AUGERS

LOGGED BY: HDR ENGINEERING, INC.


## KEY:

SI - SCREEN  
SS - SPLITSPOON  
SPT - SOIL PENETRATION  
TEST-N NUMBER  
ST - SHELBY TUBE  
T - TYPE  
WL - WATER LEVEL



# MONITORING WELL INSTALLATION DIAGRAM

PEIZOMETER NO.: MW-II-7  
BORING NO.: II-7  
JOB NO.: 8770-00 -018  
PREPARED BY: C. LEE  
CHECKED BY: C. LEE  
DATE: \_\_\_\_\_



**HDR**

HDR Engineering, Inc.

REMARKS: ALL MEASUREMENTS TO THE NEAREST 0.1 FT.



**WELL CONSTRUCTION RECORD**

FOR OFFICE USE ONLY

Quad No. \_\_\_\_\_ Serial No. \_\_\_\_\_  
Lat. \_\_\_\_\_ Long. \_\_\_\_\_  
Minor Basin \_\_\_\_\_  
Basin Code \_\_\_\_\_  
Header Ent. \_\_\_\_\_ GW-1 Ent. \_\_\_\_\_

DRILLING CONTRACTOR: BADGER DRILLING

DRILLER REGISTRATION NUMBER: 1486

STATE WELL CONSTRUCTION  
PERMIT NUMBER: \_\_\_\_\_

1. WELL LOCATION: (Show sketch of the location below)

Nearest Town: CLEMENS BORO NC.

(Road, Community, or Subdivision and Lot No.)

County: \_\_\_\_\_

Depth  
From To

Drilling Log  
Formation Description

2. OWNER:

ADDRESS: WHITE ST. CARMEL

Street or Route No.

City or Town

State

Zip Code

3. DATE DRILLED: 9-13

USE OF WELL: MANFOLDING

4. TOTAL DEPTH: 32.0

CUTTINGS COLLECTED: ☒ Yes ☐ No

5. DOES WELL REPLACE EXISTING WELL? ☐ Yes ☒ No

6. STATIC WATER LEVEL: \_\_\_\_\_ FT.

Above

Below

TOP OF CASING,

TOP OF CASING IS: \_\_\_\_\_ FT.

ABOVE LAND SURFACE.

7. YIELD (gpm): N/A

METHOD OF TEST: AIR

8. WATER ZONES (depth): N/A

9. CHLORINATION: Type N/A

Amount \_\_\_\_\_

10. CASING:

From	To	Depth	Diameter	Wall Thickness or Weight/Ft.	Material
2.5	17.0	14.5	2"	34.4	PVC
From	To	Depth	Diameter	Wall Thickness or Weight/Ft.	Material
From	To	Depth	Diameter	Wall Thickness or Weight/Ft.	Material

If additional space is needed use back of form.

LOCATION SKETCH

(Show direction and distance from at least two State R. or other map reference points).

11. GROUT:

From	To	Depth	Material	Method
0.0	13.0	13.0	PORTLAND CEMENT	SURVEY
From	To	Depth	Material <td>Method</td>	Method
From	To	Depth	Material <td>Method</td>	Method


12. SCREEN:

From	To	Depth	Diameter	Slot Size	Material
17.0	32.0	15.0	2"	1/16"	PVC
From	To	Depth	Diameter	Slot Size	Material
From	To	Depth	Diameter	Slot Size	Material

13. GRAVEL PACK:

From	To	Depth	Size	Material
15.0	32.0	17.0	#2	
From	To	Depth <td>Size <td>Material</td> </td>	Size <td>Material</td>	Material
From	To	Depth <td>Size <td>Material</td> </td>	Size <td>Material</td>	Material

14. REMARKS: BENTONITE SEAL 13' TO 15.0'



I DO HEREBY CERTIFY THAT THIS WELL WAS CONSTRUCTED IN ACCORDANCE WITH 15 NCAC 2C WELL CONSTRUCTION STANDARDS, AND THAT A COPY OF THIS RECORD HAS BEEN PROVIDED TO THE WELL OWNER.


SIGNATURE OF CONTRACTOR OR AGENT

DATE

9-13-94

# MONITORING WELL INSTALLATION DIAGRAM

PEIZOMETER NO.: MW-II-8  
 BORING NO.: II-8  
 JOB NO.: 6770-00 -018  
 PREPARED BY: C. LEE  
 CHECKED BY: C. LEE  
 DATE: \_\_\_\_\_



## HDR

HDR Engineering, Inc.

REMARKS: ALL MEASUREMENTS TO THE NEAREST 0.1 FT.



# COMPLETION REPORT OF WELL No. II-12


Sheet 1 of 1

PROJECT: White Street Landfill  
PROJECT NO: 1584-98-081  
PROJECT LOCATION: Greensboro, North Carolina

WATER LEVEL:

DRILLING CONTRACTOR: M. Moseley  
DRILLING METHOD: 4 1/4" H.S.A.  
DATE DRILLED: 3/22/05

LATITUDE:  
LONGITUDE:  
TOP OF CASING ELEVATION:  
DATUM: MSL  
LOGGED BY: L. Butler



MONITORING WELL 1584-98-081 WHITE STREET LANDFILL GPJ S&ME GDT 4/18/05



3718 Old Battleground Road  
Greensboro, NC

COMPLETION REPORT OF  
WELL No. II-12

Sheet 1 of 1

PROJECT NO: 6770-021-018

BORING NUMBER: MW-13

PAGE: 1

DATE: 1/6/93

**KEY:**  
 SI - SCREEN  
 SS - SPLITSPOON  
 SPT - SOIL PENETRATION  
 TEST-NUMBER  
 ST - SHELBY TUBE  
 T - TYPE  
 WL - WATER LEVEL


**HDR**



# WELL COMPLETION LOG

SEP 21 1994

LOCATION: GREENSBORO NC WORK ORDER # HDR  
WHITE STREET LANDFILL HDR  
 CLIENT: HDR DATE 9-12-94 CHARLOTTE, N.C.  
 WELL NUMBER: MW-14 CONTACT: CHARLIE LEE  
 INSTALLED BY: CHIEFS Aiken  
 OTHER SERVICES PERFORMED: \_\_\_\_\_



\_\_\_\_ FLUSH MANHOLE  
☒ ABOVE GRADE PROTECTOR  
 \_\_\_\_ NONE

CONCRETE 3 BAGS  
 CEMENT GROUT \_\_\_\_\_ BAGS

RISER - TYPE SCH 40 PVC  
 SIZE 2"

BENTONITE 1 by Hole Plug

SCREEN - TYPE SCH 40 PVC  
 SIZE 2" : 010 SGT

FILTER TYPE #2

DEVELOPMENT: BAILED \_\_\_\_\_, PUMPED \_\_\_\_\_, AIR LIFT \_\_\_\_\_, SURGE \_\_\_\_\_, SWAB \_\_\_\_\_, NONE \_\_\_\_\_  
 TOTAL TIME: \_\_\_\_\_ TOTAL GALLONS: \_\_\_\_\_  
 WATER APPEARANCE: START \_\_\_\_\_ FINISH \_\_\_\_\_

17W-14

# WELL CONSTRUCTION RECORD

FOR OFFICE USE ONLY

Quad No. \_\_\_\_\_ Serial No. \_\_\_\_\_  
Lat. \_\_\_\_\_ Long. \_\_\_\_\_ Pc \_\_\_\_\_  
Minor Basin \_\_\_\_\_  
Basin Code \_\_\_\_\_  
Header Ent. \_\_\_\_\_ GW-1 Ent. \_\_\_\_\_

DRILLING CONTRACTOR: BADGER DRILLING

DRILLER REGISTRATION NUMBER: 1486

STATE WELL CONSTRUCTION  
PERMIT NUMBER: \_\_\_\_\_

1. WELL LOCATION: (Show sketch of the location below)  
Nearest Town: GREENSBORO N.C.

(Road, Community, or Subdivision and Lot No.)

County: \_\_\_\_\_  
Depth From \_\_\_\_\_ To \_\_\_\_\_  
Drilling Log Formation Description

2. OWNER: \_\_\_\_\_  
ADDRESS: \_\_\_\_\_

3. DATE DRILLED: 9-12-94 City or Town RALEIGH State NC Zip Code \_\_\_\_\_  
USE OF WELL: HAZARDOUS WASTE

4. TOTAL DEPTH: 32.0 CUTTINGS COLLECTED: Yes ☒ No ☐

5. DOES WELL REPLACE EXISTING WELL? Yes ☒ No ☐

6. STATIC WATER LEVEL: \_\_\_\_\_ FT. Above \_\_\_\_\_ Below \_\_\_\_\_ TOP OF CASING,  
TOP OF CASING IS: 2.5 FT. ABOVE LAND SURFACE.

7. YIELD (gpm): N/A METHOD OF TEST: AIR

8. WATER ZONES (depth): N/A

9. CHLORINATION: Type N/A Amount \_\_\_\_\_

10. CASING:

From	To	Depth	Diameter	Wall Thickness or Weight/Ft.	Material
From <u>2.5</u>	To <u>17.0</u>	Ft. <u>14.5</u>	<u>2"</u>	<u>Sch 40</u>	<u>PVC</u>
From _____	To _____	Ft. _____	_____	_____	_____
From _____	To _____	Ft. _____	_____	_____	_____

If additional space is needed use back of form.

11. GROUT:

From	To	Depth	Material	Method
From <u>0.0</u>	To <u>13.0</u>	Ft. <u>13.0</u>	<u>PORTLAND CEMENT</u>	<u>SLURRY</u>
From _____	To _____	Ft. _____	_____	_____

12. SCREEN:


From	To	Depth	Diameter	Slot Size	Material
From <u>17.0</u>	To <u>32.0</u>	Ft. <u>15.0</u>	<u>2"</u>	<u>10/10</u>	<u>PVC</u>
From _____	To _____	Ft. _____	_____	_____	_____
From _____	To _____	Ft. _____	_____	_____	_____

13. GRAVEL PACK:

From	To	Depth	Size	Material
From <u>15.0</u>	To <u>32.0</u>	Ft. <u>17.0</u>	<u>#2</u>	_____
From _____	To _____	Ft. _____	_____	_____

14. REMARKS: BENTONITE SEAL 13.0' to 15.0'

LOCATION SKETCH  
(Show direction and distance from at least two State Roads, or other map reference points).



I DO HEREBY CERTIFY THAT THIS WELL WAS CONSTRUCTED IN ACCORDANCE WITH 15 NCAC 2C WELL CONSTRUCTION STANDARDS, AND THAT A COPY OF THIS RECORD HAS BEEN PROVIDED TO THE WELL OWNER.

SIGNATURE OF CONTRACTOR OR AGENT

DATE

Submit original to Division of Environmental Management and copy to well owner.

LOCATION: GREENSBORO, N.C.

BORING NUMBER: B-14  
MW-14

PAGE: 1

## BORING LOG


DATE: 9/12/94

NUMBER	DEPTH	SPT	T	WL	SI	DESCRIPTION (USCS)	COMMENTS
	4'						
SS-1		7-7 9-12	SS			RED ORANGE SL. SANDY, CLAYEY SILT, EQUIGRANULAR.	GRANITIOD
	8'						
SS-2	12'	4-5 5-4	SS			DK. RED COARSE SANDY CLAYEY SILT EQUIGRANULAR TO 10.5, THEN RED ORANGE-TAN, SL. MIC. SILT, TR. SAND WEAKLY FOLIATED GRANTIOD QNEISS, ~10% QZ, OCC BLACK VEIN.	GRANITIOD GNEISS
SS-3	16'	4-6 6-8	SS			RED ORANGE MIC. CLAYEY SILT TO FOLIATED TAN ORANGE SL. MIC. SANDY SILT TO FG YELLOW BRN SILT W/BLACK Mnox FRACT.	
SS-4	20'	6-6 5-6	SS			YELLOW BRN FINELY FOLIATED CLAYEY SILT, LIL Fe Ox, Mnox FRACT.	INITIAL WL @ 20.0' SCHIST.
	24'						
SS-5		2-5 5-6	SS			FOLIATED YELLOW BROWN FOL. SILT AS ABOVE TO 25.4 THEN WHITE AND BRN SPOTTED SL. SANDY EQUIGRANULAR SILT, T. MICA	GRANITE
	28'						
SS-6	32'	5-10 12-15	SS			AS ABOVE, GRANITE	GRANITE
						EOH @ 32.0'	
	36'						
	40'						
BOREHOLE COMPLETION: 32.0' BELOW GRADE							<b>KEY:</b> SI - SCREEN SS - SPLITSPOON SPT - SOIL PENETRATION TEST-N NUMBER ST - SHELBY TUBE T - TYPE WL - WATER LEVEL  <b>HDR</b>
WATER DEPTH: ~ 20.0'							
DRILLING METHOD: HOLLOW STEM AUGERS							
LOGGED BY: HDR ENGINEERING, INC.							
DATE: 9/12/94							

DATE: 9/12/94

# MONITORING WELL INSTALLATION DIAGRAM

PEIZOMETER NO.: MW-14  
BORING NO.: B-14  
JOB NO.: 6770-00 -018  
PREPARED BY: C. LEE  
CHECKED BY: C. LEE  
DATE: \_\_\_\_\_



# HDR

HDR Engineering, Inc.

REMARKS: ALL MEASUREMENTS TO THE NEAREST 0.1 FT.



3718 Old Battleground Road  
Greensboro, North Carolina 27410  
Phone: (336) 288-7180  
Fax: (336) 288-8980

## LETTER OF TRANSMITTAL

**Date:** 12/14/07  
**Project Number:** 1584-98-081  
**From:** Connel Ware

---

**To:** North Carolina Department of  
Environment and Natural  
Resources  
401 Oberlin Road  
  
Suite 150  
  
1646 Mail Service Center  
Raleigh, North Carolina 27699-  
1646

**Copy to:** Chris Marriott

Environmental Services Department  
City of Greensboro  
White Street Landfill  
2503 White Street  
Greensboro, NC 27405

**Attention:** Ms. Jackie Drummond  
**Subject:** White Steet Landfill  
Revised Water Quality Monitoring Plan  
Phase I and II Areas



**Transmitted via**  
**First Class Mail** ☐ **Overnight Express** ☒ **Hand Delivery** ☐ **Other** ☐

**Remarks:**

---

Jackie,  
The Revised Groundwater Monitoring Plan for Phase I, and Phase II Areas of the White Street Landfill is included with this Transmittal Letter. Call me if you have any questions or need any additional information.

-Connel Ware